D'MATEK TECHNOLOGY LIMITED · CONNECTED ESTATE

Internet-Ready Homes

Network pre-wiring for residential developments

Internet connectivity is now as essential to a home as electricity. Just as every modern building is wired for power during construction, D'Matek installs professional network cabling at the same stage, so homes are ready for how people live today: streaming, remote work, smart devices and reliable whole-home Wi-Fi.

THE PROBLEM IT SOLVES

- Single Wi-Fi routers cannot cover larger homes, leaving dead zones in bedrooms and upper floors.
- Wi-Fi extenders are unreliable and cut connection speeds significantly.
- Running cables after a building is finished means cutting into finished walls: expensive, messy and disruptive.
- Unlike commercial buildings, residential developments rarely plan for structured network cabling.
- Homeowners are left to find their own inadequate, unattractive fixes after moving in.

WHAT WE INSTALL

- Professional Cat6 / Cat6a structured cabling throughout the home
- Dedicated network (LAN) ports in bedrooms, living areas, kitchen and study
- A central network cabinet for clean, organised cable management
- Full testing and certification of every cable run
- Infrastructure that supports gigabit speeds today and higher speeds for years to come

Smaller homes may only need a single well-placed access point. Larger homes benefit most, which is exactly where extenders struggle and where pre-installed wiring makes the biggest difference.

INSTALLATION PROCESS

The process fits into the construction schedule, running alongside electrical work rather than after it, so it adds no delay to project completion.

1. Planning

PRE-CONSTRUCTION

Review architectural drawings, design the network layout, and mark cable routes and port locations room by room.

2. Rough-in

WALL FRAMING, ALONGSIDE ELECTRICAL

Install conduits and cable trays before plastering begins, timed with the electrical rough-in.

3. Cable pull

AFTER PLASTERING, BEFORE PAINTING

Pull cables through the conduits and install wall boxes at each network point.

4. Termination

FINISHING STAGE

Fit wall plates, terminate all cables in the central cabinet, and organise with a professional patch panel.

5. Testing and handover

PRE-HANDOVER

Certify every cable run, document the full system, and hand over a ready-to-use network. The homeowner simply plugs in a router.

Typical duration: 2–3 days per unit during rough-in, plus 1 day for termination and testing after painting.

FOR DEVELOPERS

- Market units as "Internet-Ready Homes", a tangible, modern differentiator in a crowded property market.
- Appeal directly to remote workers, young professionals and tech-conscious families.
- Give sales teams a concrete feature to show, not just describe.
- Installed with minimal disruption, during a phase when the site is already open for wiring work.
- No re-entry into finished units and no cutting into completed walls.

AFTER HANDOVER: ESTATELINE

EstateLine is D'Matek's internet service for estates. Once an estate is handed over, the same relationship that planned its network extends into ongoing, estate-wide internet service, delivered through ISP partnerships. Residents connect to a professionally planned network instead of each arranging their own provider and digging up the estate again.